

## **Publish Quotation Item for non SSR Items**

The Quotation rates toward the works of “Widening of road from Azeem Hotel ( Shoaib hotel) to church road, Balapur” and “Widening and development of 100 feet wide road from Bandlaguda junction to Errakunta junction” are invited and the details of the items to be quoted were uploaded in GHMC website “<https://www.ghmc.gov.in>”. It is requested to please refer to the website.

  
29/8/2024  
Executive Engineer,  
PDSZ-I. GHMC  
  
29/8/24

**Executive Engineer, Projects Division, South Zone-1, GHMC**

**Publish for Quotation Item for non SSR items**

**Mail id: eeghmcpdsz1@gmail.com**

Kindly publish the quotation items for non SSR items which are as follows:

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
|---|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1 | <b>Seperation Membrane :</b><br>Supply and delivery of 125 microns separation membrane polythene sheet including cost and conveyance charges etc., complete for finished item of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| 2 | <b>VDCC:</b><br>Vacuum drying of freshly laid cement concrete floor using 100% air tight suction of suitable size and length, vacuum pump to maintain vacuum pressure 0.70 - 0.80, atmospheres as per the standard procedure, floating with power floater, mechanical travelling, finishing with sound edge and corners, including hire and operational charges of machinery, labour, fuel etc., complete for finished item of work.                                                                                                                                                                                                                                                                                                                                                                     |
| 3 | <b>Groove Cutting:</b><br>Groove cut joints for freshly laid concrete pavement including cost and conveyance of all materials and labour charges etc., complete for finished item of work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| 4 | Supply of pre- cast CC blocks for kerbing made with rubberized moulds of M30 grade Design mix with 350 kgs Cement/ Cum of concrete, 20mm to 6mm nominal size (SS 5) Hard Granite machine Crushed metal @ 0.80 Cum of concrete and sand @ 0.40 Cum. of concrete for RCC works including cost and conveyance of all materials like cement, sand, coarse aggregate and water etc., to site and labour charges for mixing, laying Concrete, tamping, vibrating, lifting curing finishing top surface including hire charges of machinery and vibrator complete for finished item of work and transportation of precast block from casting site to work site of each 0.60m length CC block as per design & specification etc., complete for finished item of work (Size: 600mmx325mmx150mm/600mmx400mmx110mm) |
| 5 | Labour charges for fixing of Pre-cast kerbing blocks true to its alignment as specified by the dept. to form divider including cost and conveyance of all materials like cement sand water etc. to site including all taxes and labour charges                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
| 6 | Supply and Delivery of DI covers of size 600mm x 600mm grating with frame of size 700mm x 700mm heavy Duty of grade D-400 manufactured as per specification BS EN 124 for manhole covers and drainage gratings suitable for carriage ways of roads (including pedestrian streets), hard shoulders parking areas for all types of road vehicles with a lead bearing capacity of 400KN including cost of material, labour charges for manufacturing loading, unloading transportation etc., excluding GST.                                                                                                                                                                                                                                                                                                 |

  
 Executive Engineer,  
 PDSZ-1, GHMC.  
 29/8/2024