

GREATER HYDERABAD MUNICIPAL CORPORATION
Invitation of Sealed quotations for repairs works of 2BHK
Housing Colonies

The 2BHK Housing colonies were inaugurated and houses allotted to the beneficiaries, however due to delay in allotment of the completed houses, some items are damaged. Therefore it is essential to take up the replacement for the damaged items like, internal water supply and sanitary fixtures etc., to make these houses habitable.

The following required items are not covered in Department SSR. Hence the sealed quotations are invited for the following items for repairs to 2BHK Housing colonies of GHMC at different locations around GHMC, Hyderabad area.

Sl. No	Description of the item	Unit	Qty	Rate
	WATER SUPPLY AND SANITARY ITEMS (Makes: Ashirvad /Astral / Truflo / Supreme)			
1	Supply and fixing of premium make CPVC Pipes of 65mm OD Pipe- SCH 40 including cost and conveyance of all materials and labour charges etc. complete.	Rmt	1	
2	Supply and fixing of CPVC couplings including cost and conveyance of all materials & labour charges etc., complete.			
i	65mm dia CPVC coupler	No	1	
ii	20mm dia (3/4") CPVC coupler	No	1	
3	Supply and fixing of CPVC Brass Elbow including cost and conveyance of all materials & labour charges etc., complete.			
i	25mm dia CPVC Brass Elbow	No	1	
ii	20mm dia (3/4") CPVC Brass Elbow	No	1	
4	Supply & Fixing of 65mm dia CPVC Elbow including cost and conveyance of all materials & labour charges etc., complete.	No	1	
5	Supply & Fixing of 25mm dia CPVC Union including cost and conveyance of all materials & labour charges etc., complete..	No	1	
6	Supply and fixing of 20mm dia (3/4") CPVC Brass FTA cost and conveyance of all materials & labour charges etc., complete.	No	1	
7	Supply and fixing of 25mm dia CPVC FTA including cost and conveyance of all materials & labour charges etc., complete.	No	1	

8	Supply and fixing of 20mm dia (3/4") CPVC plain TEE including cost and conveyance of all materials & labour charges etc., complete.	No	1	
9	Supply and fixing of 63mm x 50mm dia (2.5" X 2") CPVC reducer including cost and conveyance of all materials & labour charges etc., complete.	No	1	
10	Supply and fixing of 63 mm PVC adopter connector including all labour charges etc., complete	No	1	
11	Supply and fixing of 50mm dia (2") G.I Nipple including cost and conveyance of all materials & labour charges etc., complete.			
i	50mm dia (2") G.I Nipple of 4" length	No	1	
ii	50mm dia (2") G.I Nipple of 9" length	No	1	
iii	50mm dia (2") G.I Nipple of 12" length	No	1	
12	Supply and fixing of 50mm dia GI 300mm long bend including cost and conveyance and labour charges etc., complete	No	1	
13	Supply and fixing of 50mm dia GI Clamp set including cost and conveyance and labour charges etc., complete	No	1	
14	Supply & Fixing of 50mm dia GI Elbow including cost and conveyance of all materials & labour charges etc., complete	No	1	
15	Supply and fixing of 50mm dia GI Hose nipple 6" length including cost and conveyance and labour charges etc., complete	No	1	
16	Supply and fixing of 3/4"(20mm dia) 3" long GI nipple including cost and conveyance and labour charges etc., complete	No	1	
17	Supply and Fixing of GI Couplings including cost and conveyance of all materials & labour charges etc., complete.			
i	50mm dia GI Coupler	No	1	
ii	20mm dia GI Coupler	No	1	
18	Supply and fixing of 50mm dia GI 90 degree bend including cost and conveyance and labour charges etc., complete.	No	1	
19	Supply and fixing of 50mm dia GI Non return valve including all labour charges etc. ,complete	No	1	
20	Removing Submersible pump set of 5HP/7.5HP/10HP, from existing Bore well (6 1/2" dia) and jointing the power supply flat cable, testing and re- installing into bore well including labour charges etc., complete (Excluding cost of flat cable)	Job	1	

21	Repair and jointing of water supply HDPE pipe line of 63mm dia including labour charges for excavation, sealing/packing the hole/leakage with heat joints, testing	Job	1	
22	Supply and fixing of RCC rectangular Inspection chambers cover with 30mm thickness of size 450 mm x 600 mm including cost of conveyance and labour charges etc., complete.	No	1	
23	Supply and fixing of RCC circular covers of 600 mm dia with 80mm thick including transportation and labour charges etc., complete for sumps	No	1	
LIGHTENING ARRESTOR				
24	<p>Removing, shifting and Re-installation of existing lightening arrestor above terrace water tank to terrace level of housing blocks "NIMBUS" lighting protection system which includes</p> <ol style="list-style-type: none"> 1. Removing of lightening arrestor from the existing position i.e., at terrace tank at top of 11th storey housing blocks. 2. Re-fixing the same in suitable position on the terrace of the 11 storey housing block to the parapet walls / external walls of building as directed by the department in cement concrete bed at base with cost of fixtures, clamps, drilling holes, nuts, bolts etc., 3. Giving necessary earthing connections to the existing earth pits. <p>Note: The rate quoted should be including cost of conveyance of all materials, labour charges etc., complete, but excluding CC bed cost and earthing wire / copper strip and other electrical items.</p>	Job	1	
For STP Drainage Line Outlet Makes: (Supreme / Ajay)				
25	Supply and fixing of premium make ECO- Drain pipe of 200mm dia SN-4 PVC-U of 6M length including cost and conveyance of all materials and labour charges etc., complete.	No	1	
26	Supply and fixing of premium make UGDS 450 X 200X 200mm straight chamber including cost and conveyance of all materials and labour charges etc., Complete.	No	1	
27	Supply and fixing of premium make UGDS 450 X 215mm Raiser with R-Seal including cost and conveyance of all materials and labour charges etc. complete	No	1	
28	Supply and fixing of premium make UGDS 450 mm GRP(10T MD) Frame and cover including cost and conveyance of all materials and labour charges etc. complete	No	1	

29	Supply & Fitting of 200mm dia (6kgf) 90 degree PVC Elbow including cost and conveyance of all materials & labour charges etc., complete	No	1	
30	Supply & Fitting of 200mm dia (6kgf) 45 degree PVC Elbow including cost and conveyance of all materials & labour charges etc., complete	No	1	
31	Supply and fitting of 65mm dia (2 1/2") SCH-80 UPVC Ball valve including cost and conveyance of all materials & labour charges etc., complete	No	1	

* **Note:** GST will be paid extra @ 18% separately for all the above items under "Works contract"

Date:

Signature of firm

Therefore sealed quotations are invited for the above items in sealed cover to be submitted / sent to the following address on or before 28 -10-2024 up to 3:00 PM

Address: O/o. Executive Engineer (Housing-3), GHMC
2nd Floor, GHMC Office Complex,
Opp. Hari Hara Kala Bhavan,
Patny Center Sec- bad-500003,
Cell No. 9963551524.



**Executive Engineer
Housing Division-3, GHMC.**