

GREATER HYDERABAD MUNICIPAL CORPORATION
Invitation of Sealed quotations for repairs works of 2BHK
Housing Colonies

The 2BHK Housing colonies were inaugurated and houses allotted to the beneficiaries, however due to delay in allotment of the completed houses, some items are damaged. Therefore it is essential to take up the replacement for the damaged items like, internal water supply and sanitary fixtures etc., to make these houses habitable.

The following required items are not covered in Department SSR. Hence the sealed quotations are invited for the following items for repairs to 2BHK Housing colonies of GHMC at different locations around GHMC, Hyderabad area.

Sl. No	Description of the item	Unit	Qty	Rate
	WATER SUPPLY ITEMS - CPVC/PVC Fittings (Makes: Sudhakar/Ashirvad /Astral /Truflo)			
1	Supply and fixing of Premium make CPVC Pipes of 110mm OD pipe-SCH-40 including cost and conveyance of all materials and all labour charges, etc., complete.	Rmt	1	
2	Supply and fixing of 110mm dia CPVC 45 degree bend including cost and conveyance of all materials & labour charges etc., complete.	No	1	
3	Supply and fixing of 110mm dia CPVC 87.50 degree bend including cost and conveyance of all materials & labour charges etc., complete.	No	1	
4	Supply and fixing of 110mm dia CPVC Couplings including cost and conveyance of all materials & labour charges etc., complete.	No	1	
5	Supply and fixing of 110mm dia GI Clamp including cost and conveyance and labour charges etc., complete	No	1	
	RCC Sump & Terrace Over head Tank Manhole Cover			
6	Manufacture, supply, delivery and fixing of Sump and Terrace tank manhole Covers made with 2mm thick GI sheet welded to 15mm x 2mm thick, MS Flat Strip around to GI cover and Base frame of MS angle of 20mmX20mmX2mm thick with powder coated. GI sheet cover and base frame is jointed with 2 nos of MS hinges and 8mm dia MS handle of 1 no and locking arrangement to base plate and GI cover with 15mm dia of plain rod of 40mm height with key hole including with necessary brick masonry with finishing cost and conveyance of all materials & labour charges etc., complete.			
	Sump and Terrace over head tank manhole covers of any size	Sft	1	

7	Supply, Delivery, Installation, Commissioning of Single phase Submersible Sewage self priming pump set for dewatering from cellar area of housing blocks (Auto Start) including cost, conveyance and labour charges, erection of pump sets with all accessories. (Makes: Suguna / CRI/Textmo) for 1.5 HP Single Phase Pump sets	No	1	
8	Removing and cleaning of mud, silt and other foreign material, garbage etc., accumulated in cellar floor including dewatering, engaging labour for cleaning and carting away the materials, including all materials and labour charges etc., complete.	Sqm	1	

*** Note: GST will be paid extra @ 18% separately for all the above items under “Works contract”**

Date:

Signature of firm

Therefore sealed quotations are invited for the above items in sealed cover to be submitted / sent to the following address on or before 13 -12-2024 up to 3:00 PM

Address: O/o. Executive Engineer (Housing-3), GHMC
2nd Floor, GHMC Office Complex,
Opp. Hari Hara Kala Bhavan,
Patny Center Sec- bad-500003,
Cell No. 9963551524.

**Executive Engineer
Housing Division-3,GHMC.**