

Quotations invited for

Repair and Rehabilitation measures for ROB works in PD-NZ, GHMC.

S. No.	Item Description	Unit
1	Making 'V' groove along the cracks on the girder & sealing the groove with epoxy putty inclusive of men, machinery & materials all complete, as directed by the Engineer-in-charge & as explained in sketch	Per Rmt
2	Lifting the Super structure of the span by using of hydraulic Pump connected to the power pack and attending the rectification works at piercap and soffit of the girder haunch excluding cost of materials for Replacement of bearing without causing any detrimental effect to any part of the bridge structure as per direction of engineer in charge	Per Span
3	Supplying, fitting and fixing in position true to line and level duly by removal of Existing bearing with electrometric bearing conforming to IRC:83 (Part-II) Section IX complete, including all accessories as per drawings and technical specification Clause 1207.1 MORD	Per Cu.cm
4	Providing and fixing along with hire charges for supporting the deck slab firmly using MS cribs for the vertical support and placing of structural steel ISMB I50 along with mechanical jacks with Horizontal bracing including cost of all incidental labour charges etc for complete item of work for Supporting super structure span of 4 Girders.	Per Span
5	Supply of compression seal expansion joint as per IRC SP-69	Mtrs
6	Supply and delivery of anticarbonation paint	Per Kg

Sealed quotations to be submitted in the office of the Executive Engineer (Project Division-NZ), Greater Hyderabad Municipal Corporation 7th Floor, Parking Complex, Abids, Hyderabad

Mail id : pd3ghmc.08@gmail.com

Contact : AEE - 7331189758

Note : The rate quoted shall be excluding GST.

**Executive Engineer,
PD-NZ, GHMC**